Scope:- These specifications are intended to cover the furnishing of all labor and materials required to clean, shellac, putty and paint all wooden, metal and masonry surfaces of the complete building; as called for and specified below.

General:- No outside painting is to be done during wet or freezing weather.

No paint is to be applied until preceding coat has become thoroughly dry.

All materials to be the best of their respective kinds and to be delivered to the building in manufacturer's unbroken containers, with analysis on each can.

Where manufacturers' names and number are given, they are indicative of the quality and composition of paint. Other well recognized paints having same composition will be considered.

All colors to differ from the preceding coat.

Structural Steel:- Thoroughly clean all surfaces, removing all dirt, rust, oil, grease, scale and other foreign materials, leaving the clean metal exposed ready to receive the paint.

All surfaces inaccessible after assembly to be wash painted before assembly.

Shop coat to be dry before shipment.

All surfaces inaccessible after erection to be painted first field coat before erection.

Second field coat not to be applied until after e-